



# AS SITE SAFETY MANAGER I LIKE TO ASK THE QUESTION?

What if we had an incident?

Could I look back and say we  
did all we could to prevent it.

# IN 2007 IT WAS DIFFICULT TO SAY THAT!

With the institution of chapter 33 new guidelines forced us to “say what if”?

Before the Crane Arrived at the site.

With CFR 1926-1400 in our sights we could enforce new guide lines.

# Kick off meeting with agendas that helped subcontractors get proper training and permits, became 1<sup>st</sup> line of a Screening Crane Work.

# Turner

MSK Phase 2 Kick off Meeting Agenda \_\_\_\_\_ Date \_\_\_\_\_

Company \_\_\_\_\_

## Future Safety Items

- a) HASP, Health and Safety Program (must be specific to trade)
- b) Name of 30 hour OSHA competent person \_\_\_\_\_
- c) Please make sure CP is familiar with the HASP you submit
- d) Can your CP be available for a Preplan safety meeting before you start work? \_\_\_\_\_
- e) **DBO2-Safetynet Verification** (If not a currently approved company, Turner will need copies of the last 2 years of subcontractors OSHA 300 logs. Final approval of new subcontractors not currently in DBO2 is subject to New York Business Unit final approval.)
- f) If scope of work is minimal in size and duration **with no apparent long term dangers**, a contractor may submit a JHA (Job Hazard Analysis) in place of item "A" (HASP). Final approval to be determined by site safety and project managers.
- g) All permits as per Chapter 33 of NY Building Code (including came, scaffold, and flammables) need to be in hand at the pre-planning meeting. Please note that permits take 3-5 weeks to process. If you have any questions concerning permits call Turner Safety Department.
- h) Note: Certain job positions require extra training and certification (i.e. Iron workers, subpart R). Please allow your workers proper time to attain the proper certifications before project start date.
- i) As of 11/8/10 all rigging and signaling with a crane of capacity of 2000 lbs. or greater requires a certified rigger & signalman. CFR 1926.1400
- j) Daily Pre-Task safety discussions handled by CP & turned in to field office by 9 am
- k) No Ladders. Only Manufactured scaffolds and Man lifts
- l) All Material must remain mobile
- m) Orientation first day
- n) Please provide a Certificate of Insurance, see attached sample. If you use subcontractors you must submit their insurance information as well.
- o) If you hire a second tier sub contractor to perform the labor they will need all the above approved before mobilization

Sign \_\_\_\_\_ Print \_\_\_\_\_ Title \_\_\_\_\_



# LAST LINE OF ENSURING **COMPLETE CRANE SAFETY**

Orientations the day company's arrive.

**NO MATTER HOW IMPORTANT**

**THE JOB.**

- ✓ All Permits Verified (CN,CD, Jump, Impact)
- ✓ Training Verified (Crane Licenses & Certifications)
- ✓ Crane Specs Verified (Drawings match job)
- ✓ Counter weight package, Plates

NOW WE DON'T FIND OURSELVES ASKING  
**“WHAT IF”? AS MUCH**



WE FIND OURSELVES  
SAYING “GOOD THING  
WE PLANNED THAT  
CRANE JOB”